Exhibit A

Minimum Criteria and Underlying Assumptions 4/8/2025

SECTION 1: MINIMUM CRITERIA

Minimum Criteria Overview

This document outlines the property criteria to be considered when evaluating potential administrative and operations center relocation options for the Portland Public School (PPS) headquarters. These criteria, to be reviewed and approved by the PPS Board, will serve as guiding tools to facilitate the identification, evaluation and selection of replacement facilities that meet PPS's organizational needs and support the delivery of high-quality services to students and families for years to come.

Over the past eight months, PPS design consultants Mackenzie and Bainbridge conducted a comprehensive assessment of the Prophet Education Center to inform the creation of these criteria, with findings outlined in the attached PEC Space and Programming Evaluation report. The study aimed to align facility requirements with the effective delivery of services to students and families by conducting a multi-phase analysis. This included benchmarking peer districts through interviews and site tours, engaging in detailed departmental interviews with PPS staff to understand operations and space needs, and conducting a comprehensive analysis that synthesized both qualitative insights and quantitative data to inform final programming recommendations. A summary of this report is on page 3 of this document.

Minimum Criteria:

- **Criteria 1: Owned not Leased**
  - Context: The District does not have the financial capacity to take on a long-term lease that would increase over time. Ownership also allows greater control over operating expenses.
- **Criteria 2: Within District Boundaries**
  - Context: The Administrative site must be within District boundaries. However, the Operations Center could be outside the boundaries if it results in a more appropriate site and any increase in average driving time is justifiable.
- **Criteria 3: Central Location**
  - Context: Given the high volume of travel between the District headquarters and schools, the location(s) should be reasonably central (relative to schools) to allow efficient travel back and forth for both PPS staff and the public.
- **Criteria 4: Easy Freeway Access**
  - Context: The location(s) needs good access to major freeways and arterials.
- **Criteria 5: Access to Public Transit**
  - Context: As part of the PPS commitment to Climate Justice, we will continue to encourage use of mass transit.
- **Criteria 6: Parking**
  - Context: The new location(s) must have a reasonable (warehouse 1:1000 SF and admin 2:1000 SF) number of on-site parking spaces correlated to the

functions at the site, including parking for visitors and families who need to access Central Office functions and Board meetings.

- **Criteria 7: Accommodates PPS Spatial and Functional Needs**
    - Context: The selected relocation options must support PEC's programming as identified through the PEC Space and Programming Evaluation report. Select parameters and assumptions are highlighted below:
        - On-site workspace for every PPS Central Office employee.(March 2025 staff count without increase or reduction; no changes to PPS operations were assumed).
        - Equivalent conference space to PEC (redistributed in quantity, size, and capacity to better align with needs).
        - Break and lunchroom space within industry standards.
        - Private office space in line with sensitive work requirements and District policy.
        - Boardroom space with equivalent seating capacity, dais, and AV capacity as PEC Boardroom
        - Operations space for current functions and inventory storage, including:
            - Fabrication & Shop Maintenance
            - Nutritional Service, including industrial kitchen
            - Warehouse
            - Chief Operating Officer (COO)
            - Office of School Modernization (OSM)
            - Security Services
            - Real Estate and Construction Management (REC)
            - Office of Technology Information Services (OTIS)
            - Loading Docks (at least 10)
            - Fleet Parking (at least 121 spaces)
- **Criteria 8: Safety**
    - Context: Site safety is critical for staff and visitors, particularly after dark.
- **Criteria 9: Cost Neutral to PPS**
    - Context: Consistent with Resolution 6861 As Adopted, the entirety of the relocation must be cost neutral to PPS.

SECTION 2: PEC PROGRAMMING AND SPACE EVALUATION SUMMARY

PEC Space and Programming Evaluation Report Context and Usage

This study produced two primary information deliverables:

1) Square footage recommendations
2) Space Programming recommendations

PPS will use the square footage recommendations to inform the general property specifications in a property search solicitation. PPS will incorporate square footage range, based on the consultant square footage recommendations, within the property solicitation to account for variability in layout and efficiency on a property-by-property basis.

Once potential properties are identified, PPS will use the programming, the spatial and functional specifications that support PPS operations, to confirm that the specific relocation option meets PPS's needs. This will be done through "test fits", which are a design process where a proposed space or building layout is tested for its feasibility.

Findings Summary:

This study contemplated three scenarios PPS may encounter when looking at market relocation options, with square footage estimates provided as general guidelines based on planning assumptions and standard multipliers to be confirmed with "test fits":

SCHEME 1:

- Combined Facility - 279,000 SF

SCHEME 2:

- Administration Facility with Operations Staff - 114,000 SF
- Operations Facility without Operations Staff - 168,000 SF

SCHEME 3:

- Administration Facility without Operations Staff - 91,000 SF
- Operation Facility with Operations Staff - 191,000 SF

	STAFF COUNT	CURRENT GROSS SQUARE FEET	MINIMUM GROSS SQUARE FEET	PERCENT REDUCTION
SCHEME 1				
SINGLE SITE	691	339,636	278,557	18%
SCHEME 2				
ADMINISTRATION	577	115,218	113,544	1.5%
OPERATIONS CENTER	114	224,418	168,121	25%
TOTAL	691	339,636	281,665	17%
SCHEME 3				
ADMINISTRATION	419	89,106	91,369	-2.5%
OPERATIONS CENTER	272	250,530	190,395	24%
TOTAL	691	339,636	281,764	17%

SPACE PROGRAMMING ASSUMPTIONS:

ADMINISTRATION SPACE ASSUMPTIONS

- Parking Ratio 2:1000 SF
- Staff counts reflected are accurate as of March 2025.
- A seat is assumed for every staff member currently assigned to PEC, a hybrid-work model was not considered.

- Departments included in Administrative HQ in Scheme 3
    - Superintendent
    - Chief of Staff
    - Finance
    - General Counsel
    - Human Resources
    - Accountability and Equity
    - Teaching and Learning
    - Student Success Services
    - School Performance
- Square footage requirements for off-site staff/functions are not included.
- Workspaces have been standardized as follows:
    - 36 sf (6x6) - standard workstation
    - 120 sf - standard office (Directors)
    - 220 sf - office with meeting space for 4-6 (Chiefs)
    - 320 sf - office with meeting space for 6+ (Superintendent only)
- The current boardroom and adjacent flex space square footage was maintained and combined to account for a more functional/flexible space.
- Conference rooms are listed as either shared or dedicated based on department programming meetings. These may fluctuate but provide design flexibility for PPS.
- The square footage allocated to conference rooms is similar to PEC but has been redistributed in quantity, size and capacity to better align with program needs.
- A lunchroom/cafeteria with cooking capabilities was not included. The cafeteria at the PEC site has not been in operation since 2020. Break room space appropriate for the staff count was listed as a lump sum to be distributed depending on the scenario and built conditions.
- An industry standard circulation multiplier of 1.55 was added to the net square footage (NSF) for all admin spaces to calculate usable square footage (USF). This is typical when the building program is predominantly workstations. However, it does not include contingency to compensate for inefficiencies in a building floor plate.
- A building gross multiplier of 1.2 was added to the usable square footage (USF) to account for exterior walls, vertical penetrations/circulation, building systems and restrooms to calculate gross square footage (GSF).
- Current building code will require more fixtures (i.e., restroom counts) than what was required when PEC was built, resulting in added square footage. New facilities will be required to meet the current building life safety code, ADA, energy code, etc. It is assumed the applied building gross multiplier will account for this deficiency.

OPERATIONS CENTER SPACE ASSUMPTIONS

- Staff counts reflected are accurate as of March 2025.
- A seat is assumed for every staff member currently assigned to PEC, a hybrid work model was not considered.
- Departments included in Operations Center in Scheme 3:
    - Fabrication & Shop; Maintenance
    - Nutritional Service
    - Warehouse
    - Chief Operating Officer (COO)
        - Office of School Modernization (OSM)

        - Security Services
        - Real Estate and Construction Management (REC)
    - Office of Technology Information Services (OTIS)
- Parking Ratio 1:1000 SF
- Fleet Parking (inclusive of boom lifts, etc) - 121 fleet vehicles
- Square footage requirements for off-site staff/functions are not included.
- An industry standard circulation multiplier of 1.15 was added to the net square footage (NSF) for all operations spaces to calculate usable square footage (USF). This is typical for a fabrication/warehouse facility. However, it does not include contingency to compensate for inefficiencies in a building floor plate.
- A building gross multiplier of 1.15 was added to the usable square footage (USF) to account for exterior walls, vertical penetrations/circulation, building systems and restrooms to calculate gross square footage (GSF).
- Current building code will require more fixtures (i.e., plumbing counts) than what was required when PEC was built, resulting in added square footage. New facilities will be required to meet the current building life safety code, ADA, energy code, etc. It is assumed the applied building gross multiplier will account for this deficiency.
- Current building code will include safety requirements for clearance areas around large equipment and a new racking system in the warehouse. These requirements are reflected in the square footage recommendation.

Shops/Maintenance

- Elimination of obsolete machinery resulted in a reduction of 30% of shop area; however new code and safety required clearances around the remaining equipment resulted in added square footage.
- This assumes that inventory of parts and storage in the shops (excluding the music shop) will be analyzed and purged by the department and reduced by an estimated 25%.
- The shops and maintenance area is comparable in size to peer districts that were reviewed by PPS and the consultants.

Warehouse

- Racking requirements for the warehouse only (excluding shops and nutritional service spaces) are generally measured by the stored volume. After minimal purging, approximately 270,000 cubic feet (includes only the racks and aisles between the racks) is estimated to be required to accommodate the existing storage and flex space needs. Based on this cubic feet, the following are the square footage needed for various clear height scenarios.
    - If a warehouse has a 30’ Clear Height - 33,000 SF (usable) of racking and circulation within the racking area. Total Warehouse requirement of 144,000 SF (gross).
    - If a warehouse has a 20’ Clear Height - 35,775 SF (usable) of racking and circulation within the racking area. Total Warehouse requirement 150,468 SF (gross).
    - If a warehouse has a 16’ Clear Height - 42,299 SF (usable) of racking and circulation within the racking area. Total Warehouse requirement 157,765 SF (gross)
- PEC currently has 25 loading docks that are not fully utilized. The recommended facility reduces the loading docks to 10 + loading docks with a dedicated loading zone.

(Loading docks are elevated from ground level and have dock levelers for safety and ease of loading. Loading zones are dedicated short term parking areas to load sprinter vans and standard vehicles.)

- Nutritional Services test kitchen was calculated based on the new Lincoln High School kitchen to be reflective of current operational needs. Per USDA requirements, and FDA regulations, Nutritional Service programmed space now includes dedicated storage for food in lieu of part of the larger warehouse storage area.
- Bond warehouse, leased warehouse, off-site storage were all excluded from the square footage recommendation. The approximate SF of off-site storage is approximately 69,826 SF (usable).

Offsite Operations

- The Transportation and Grounds Maintenance departments, which are currently located offsite of the Prophet Center were excluded from the square footage recommendation and are expected to stay in their current locations. Their anticipated needs are approximately 37,078 SF (gross) of building and an additional 150 bus parking stalls and 105 employee parking stalls.